



HUNTSVILLE

Kathy Martin, P.E.
Director
City Engineer

Urban Development Department
Engineering Division

JOHN HUNT PARK DRAINAGE IMPROVEMENTS, PHASE II

Project No. 65-15-SP38

October 17, 2016

Addendum #2

Attachment "A" is amended as follows:

Replace bid quantities with "replacement", **Attachment "A1"**. Please use the revised attachment to submit bid pricing; **all bids must be submitted using Attachment "A1"**. Contractors are authorized to download revised quantities from website and paste to a CD-RW (preferably in a live/flash drive format) which must be submitted with the original bid packet. In addition, two hard copies must be signed and submitted with original bid packet. Bid must be submitted from the file (Quantities) provided and downloaded from the City of Huntsville's website. Failure to do so may be cause for rejection of bid. The City reserves the right to reject any altered bid resulting from altering the bid CD in any manner. Contractors should be mindful of making changes to formatting already established in column for Bid Unit Price, as it may affect the outcome of their bid. In order to verify calculations are correct, Contractor may choose to manually multiply those unit costs x bid quantities to ensure extensions are correct, prior to printing and submitting with bid packet. If a price discrepancy is found on the CD-RW, or the correct version of bid quantities is not submitted on the CD-RW which corresponds to the printed hard copy, then printed hard copy prices submitted with original bid documents, with Contractor signature, will prevail. However, calculations must be accurate and will be verified manually.

- Any bidder who designates a change on the outside of the envelope understands that any deletions or additions designated, bidder must further indicate the particular bid item relative to the deletion or addition, even if the deletion or addition references to deduct or add to the Total Base Bid.

QUANTITIES REVISIONS

Delete

~~4 Soldier Pile Retaining Wall 47 CY~~

Add

4 Soldier Pile Retaining Wall 53 SY

The Star of Alabama

CLARIFICATIONS

Geotextile filter for Aggregate Slope Protection shall be used under stabilized construction entrance and other areas where aggregate drives may be required, as directed by engineer.

Design calculations for soldier pile wall will be provided to awarded Contractor to hold on-site, as per OSHA requirements.

For none traffic areas, Contractor will be required to backfill culvert with rock one (1) foot around sides and top. Additional area excavated for culvert will be backfilled with soil generated from culvert excavation and compacted to the satisfaction of the engineer. In areas exposed to traffic (roads and parking lot section), entire excavation shall be backfilled with rock to one (1) foot above culvert top slab.

Shoring will be paid for in square yards of exposed wall, measured from excavation grade side to top of wall. Top of wall shall be constructed to 18" above highest adjacent grade.

Toe walls shall be standard 2.5 foot depth wall and shall be constructed on both ends of culvert. Toe wall construction shall be considered subsidiary to culvert item.

Q: Is it 5% retainage or 5% of 50% retainage held?

A: Refer to Section No. 12 in the Supplement to General Requirements in the Specifications.

Q: General Contractors license required is (MU) Municipal & Utility or (HS) Highways & Streets; will a MU-S license suffice?

A: Per the State of Alabama Licensing Board for General Contractors, if the majority of the work being performed falls under a MU-S classification, then that license will suffice.

Addenda will only be emailed to those bidders who attend and have signed in at the pre-bid meeting. All addenda, as well as other project information, are available for downloading on Engineering's website at www.huntsvilleal.gov/engineering/bidlist. Acknowledgement of receipt/download from website of addenda is mandatory using Attachment "C" located in the Specifications and attachment must be submitted with bid package. Failure to do so shall be cause for rejection of the bid. It is the responsibility of all bidders to refer to the website for any updates. The attached pre-bid meeting minutes, all addenda and attachments for the above-referenced project will become part of the contract documents.

Attachments: Revised Quantities-Attachment A1

END OF ADDENDUM #2

ATTACHMENT "A1"					10/17/2016
John Hunt Park Drainage Improvements, Phase II					
Project No. 65-15-SP38					
UNIT BID SHEET					
ITEM NO.	DESCRIPTION	BID QTY	BID UNIT	BID UNIT PRICE	BID AMOUNT
1	Site Prep and Demolition (Includes Clearing & Grubbing, All Demolition and Proper Disposal)	1	LS		\$0.00
2	Double 10ft x 8ft Reinforced Concrete Box Culvert, Complete In Place (6'-12' Fill Height). To Include bedding and back filling and with rock to 1 foot above culverts top slab.	716.00	LF		\$0.00
3	Reinforced Concrete Box Culvert Wing Walls, (2 Wings)	1.00	EA		\$0.00
4	Soldier Pile Retaining Wall	53	SY		\$0.00
5	Concrete Wash Pad	1	LS		\$0.00
6	Mobilization	1	LS		\$0.00
7	Geotextile Filter For Aggregate Slope Protection	1,190	SY		\$0.00
8	15" Concrete Headwall with Duckbill Valve, Complete In Place	1	EA		\$0.00
9	15" Concrete Headwall, Complete In Place	1	EA		\$0.00
10	634A000, Industrial Fence, 4 Feet High	74	LF		\$0.00
11	634A002, Industrial Fence, 6 Feet High	33	LF		\$0.00

ATTACHMENT "A1"					10/17/2016
John Hunt Park Drainage Improvements, Phase II					
Project No. 65-15-SP38					
UNIT BID SHEET					
12	634B003, Industrial Fence, 12 Feet High Plus Barbed Wire (45 Degree Arms)	326	LF		\$0.00
13	Erosion Control Product, Type S1 (NAG S150)	1,185	SY		\$0.00
14	Silt Fence	2,500	LF		\$0.00
15	Silt Fence Removal	2,500	LF		\$0.00
16	Rock Check Dam (includes culvert inlet protection inside pond)	5	EA		\$0.00
17	48" Connection into Box Culvert and one stick of pipe	1	Each		\$0.00
18	36" Connection into Box Culvert and one stick of pipe	1	Each		\$0.00
19	Aggregate Surfacing (ALDOT#1) for Construction Entrance misc use	100	TON		\$0.00
20	Wattle	200	LF		\$0.00
TOTAL BASE BID					\$0.00

ATTACHMENT "A1"				10/17/2016
John Hunt Park Drainage Improvements, Phase II				
Project No. 65-15-SP38				
UNIT BID SHEET				
ALL ITEMS SHALL BE CONSIDERED IN-PLACE. PRICES SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND REMOVALS AS REQUIRED FOR CONSTRUCTION OF THE REQUIRED WORK.				
COMPANY _____ SIGNATURE _____ DATE _____				